Status Update

David P. Lusch, Ph.D.

Department of Geography and Institute of Water Research Michigan State University

Ottawa County 9th Annual Water Quality Forum – Nov. 7, 2014

Administrivia

- July 8, 2014 Ottawa County Board of Commissioners approved and authorized the Phase-2 contract with MSU.
- > August 26, 2014 Contract start date.
- September 17, 2014 Ottawa County Groundwater Task Force approved the chloride sampling protocol.
- September 19, 2014 Public Kick-Off meeting at the Fillmore Street complex.

Current Tasks and Achievements

- > Groundwater sampling for chloride concentration
 - Two rounds of sampling from volunteer sites completed
 - Saturday, September 27 and Saturday, October 11
 - 293 lab tests performed using EPA Standard Method 9212







- **Current Tasks and Achievements**
 - > Groundwater sampling for chloride concentration
 - Round 1 (core area) Saturday, September 27
 - 120 samples were tested in the lab
 - 25 samples (20.8%) exceeded 250 mg/L
 - <u>66 rock wells</u> 14 (21.2%) exceeded 250 mg/L [exceedance values ranged 251 – 1,855 mg/L]
 - <u>7 deep glacial wells</u> <u>3 (42.9%) exceeded 250 mg/L</u> [exceedance values ranged 330 – 1,273 mg/L]
 - <u>31 glacial wells</u> 6 (1.9%) exceeded 250 mg/L [exceedance values ranged 257 – 1,502
 - 16 well type unknown 2 (12.5%) exceeded 250 mg/L [exceedance values ranged 276 – 279]

- **Current Tasks and Achievements**
 - > Groundwater sampling for chloride concentration
 - Round 2 (peripheral area) Saturday, October 11
 - 173 samples were tested in the lab
 - 11 samples (6.4%) exceeded 250 mg/L
 - <u>57 rock wells</u> 6 (10.5%) exceeded 250 mg/L [exceedance values ranged 282 – 926 mg/L]
 - <u>12 deep glacial wells</u> **1 (8.3%) exceeded 250 mg/L** [exceedance value = 523 mg/L]
 - <u>70 glacial wells</u> **2 (2.9%) exceeded 250 mg/L** [exceedance values ranged 263 – 534
 - 34 well type unknown 2 (5.9%) exceeded 250 mg/L [exceedance values ranged 954 – 1,023]

- **Current Tasks and Achievements**
 - Bedrock aquifer test planning
 - Seven sites were evaluated
 - Publically-owned
 - Within a chloride "hotspot" as determined in Phase-1
 - Relatively few water wells within 2,500 feet
 - Trafficable soils for drilling rig and support trucks
 - Proximity to county drain or river to discharge pumped water
 - Selected site: water tower parcel, 96th Ave at Polk St.
 - Draft RFP for drilling contractors is currently under review
 - I test well + 2 monitoring wells drilled & completed by mid-December
 - Aquifer test completed early January

Current Tasks and Achievements Bedrock aquifer test planning



Current Tasks and Achievements

Bedrock aquifer test planning



Current Tasks and Achievements

Bedrock aquifer test planning

Drawdown using T = 737 ft²/day



Current Tasks and Achievements Bedrock aquifer test planning



- **Current Tasks and Achievements**
 - Monitoring well equipment purchased & received
 - Two Schlumberger Water Services CTD Divers
 - SWL: +/- 5 cm (barometric compensation provided)
 - Conductivity: 0 120 mS/cm +/- 1% of reading
 - Temperature: 0 50 °C +/- 0.1 °C
 - Sampling interval: user adjustable 1 sec 99 hours



Current Tasks and Achievements

- Streamflow measurements
 - Reconnaissance of optimal measurement sites completed
 - Stream measurements scheduled to begin next week
 - Large stream (ADCP) and small stream ADV equipment is ready for deployment
 - Teledyne RD Instruments Sentinel ADCP
 - Profiling range 1 165 meters
 - SonTek Argonaut-ADV (acoustic doppler velocimeter)

- Low velocity down to 0.003 ft/s -Bhallow water down to 3 cm depth







- **Current Tasks and Achievements**
 - Compilation of PAWS model input parameters
 - Ottawa Co. LiDAR DEM Obtained
 - National Hydrography Dataset Obtained
 - CDL / NLCD 2013 Land Use /Land Cover Obtained
 - NRCS Digital Soils Obtained
 - NexRad, sub-daily, precipitation data not yet downloaded
 - Streamflows not yet measured
 - Groundwater Heads (USGS + Wellogic data) Obtained
 - Subsurface Heterogeneity not yet completed

Current Tasks and Achievements

Preliminary IGW conceptual model is being tested



Status Update

David P. Lusch, Ph.D.

Department of Geography and Institute of Water Research Michigan State University